

AUTO-COUPLING WET WELL REMOVAL SYSTEM




AUTO-COUPLING WET WELL REMOVAL SYSTEM



(GRIND HOG OMITTED)

DIMENSIONAL DETAIL

| MODEL | DIMENSIONS – IMPERIAL/METRIC | | | | | | | | | | | | | | |
|--|------------------------------|-----|---------|-----|--------------------------------|-----|---------|-----|---------|------|---------------------------------------|--------------------|-----|---------------------|-----|
| in the second se | DIM "A" | | DIM "B" | | DIM "C" | | DIM "D" | | DIM "E" | | DIM "F" | LIFTING WEIGHTS | | CAPACITY RATINGS | |
| | IN. | MM. | IN. | MM. | IN. | MM. | IN. | MM. | IN. | MM. | . Wet Well Dimensions by others | LBS. | KG. | GPM | L/S |
| 7AS-8 | 36 | 914 | 36 | 914 | 25 ¹ / ₄ | 641 | 30 | 762 | 34 | 863 | | 350 | 160 | 315 | 20 |
| 10AS-8 | 36 | 914 | 36 | 914 | 28 ³ /4 | 730 | 36 | 914 | 41 | 1041 | | 550 | 250 | 850 | 54 |




VARIABLES

- Elevations
- Wet Well Diameter / Dimensions
- Hatch Locations
- Guide Rail Supports required when over 10'

COMPONENT LIST

| ITEM | PART NO. | DESCRIPTION | MAT'L | QTY. | | | | | | |
|-------------------|----------|--------------------------|-------|----------|--|--|--|--|--|--|
| 1 | 185185 | AUTO-COUPLING BASE-8" | C.I. | 1 | | | | | | |
| 2 | 185186 | AUTO-COUPLING FLANGE-8" | C.I. | 1 | | | | | | |
| 3 | 185188 | SLIDE RAIL UPPER BRACKET | S.S. | 1 | | | | | | |
| 4 | 185189 | SLIDE RAIL GUIDE | S.S. | 2 | | | | | | |
| 5 | 185191 | LOWER WALL BRACKET | S.S. | 2 | | | | | | |
| 6 | 185192 | SLIDE RAIL | S.S. | 2 | | | | | | |
| 7 | 185187 | OVERFLOW | PVC | 1 | | | | | | |
| 8 | 185194 | UPPER WALL BRACKET | S.S. | 2 | | | | | | |
| 9 | 185201 | HATCH ASSEMBLY | AL | OPTIONAL | | | | | | |
| 10 | 185203 | LIFTING HARNESS | S.S. | 1 | | | | | | |
| 11 | 185202 | HOIST | S.S. | OPTIONAL | | | | | | |
| HARDWARE ITEMS | | | | | | | | | | |
| 12 | 185074 | GASKET | RR | 1 | | | | | | |
| 13 | 185195 | BOLT | S.S. | 8 | | | | | | |
| 14 | 185196 | L / WASHER | S.S. | 8 | | | | | | |
| 15/20/24/25/27 | 185197 | BOLT | S.S. | 27 | | | | | | |
| 16/19/23/26/28/30 | 185200 | F / WASHER | S.S. | 39 | | | | | | |
| 17/22/31 | 185160 | L / WASHER | S.S. | 14 | | | | | | |
| 18/21/32 | 185199 | NUT | S.S. | 14 | | | | | | |
| 29 | 185198 | NUT | S.S. | 12 | | | | | | |





G.E.T. INDUSTRIES INC. P.O. Box 640, Brampton, Ontario Canada L6V 2L6 T (905) 451-9900 F (905) 451-5376 www.grindhog.com e-mail: get@grindhog.com

PROJECT

Drewville Road Pump Station Carmel, NY

DASX

J. Robert Folchetti & Associates, L.L.C. Somers, NY

TM.

CONTRACTOR

Brennan Construction Co. Mahopac, NY

represented by: